



ASKAP project update

ATUC

Antony Schinckel | ASKAP Director

2 June 2014

CSIRO ASTRONOMY AND SPACE SCIENCE

www.csiro.au



ASKAP - BETA Operations

- Regular observing from the SOC
- 6 antennas (1, 3, 6, 8, 9, 15) , Mk I PAFs
- 9 dual polarisation beams
 - 16,416 spectral channels over 304 MHz
- Mk I PAF performance as expected (above 1100 MHz degrades, Tsys at 1500 2.8x 900 MHz value)
- Antenna locations known to few mm
- Pointing: more work needed on pointing model
- Third axis rotation used regularly – seems important to cleanliness of images (primary beam)
- Data captured at MRO, transferred to Pawsey
 - ASKAPSoft, also miriad, CASA, DIFMAP etc
- CASDA progressing

ASKAP Highlights


- ACES team expansion
 - Members from Operations, Astrophysics, and external members from SSTs
 - Busy days in SOC
- Several “firsts” :
 - 6 antenna continuum image
 - 6 antenna spectral line data cube
 - Comparison with other telescopes images e.g SUMSS, LVHIS
 - B1830-211 – redshifted HI absorption at 753MHz
 - NGC253 (11 hours, c.f. ATCA image)
 - etc
 - Very high signal-to-noise results (up to 50,000:1 on cluster field ?)
 - Dave to present

ASKAP Highlights

- Mk II Prototype
 - Assembly, testing and verification process (RFI)
 - More testing here at Marsfield rather than MRO
- Commissioning – increased use of remote (SOC) observing
- “Galaxy” at Pawsey now live
 - ASKAPsoft etc installed
 - Used for most of the imaging
- Large scale procurements for 30 Mk II PAFs underway
 - Procurement of parts – over 6 million individual parts
- Some schedule slippage due to:
 - Prototype completion – faulty chequerboard, RFI testing etc
 - Procurement processes
 - (CSIRO re-structure and budget ?)



PAF wins

Engineering excellence





Mk II PAF

Full size prototype assembly, verification, test



PAF performance (Ap A)

Small scale prototype – 5 x 4




ASKAP Mk II Prototype – RFI testing

- Successful stress/integrated testing of the ADE Back End systems & EMC testing of active front end
- First end to end testing of full-size PAF prototype conducted successfully



ADE Prototype

- Recent progress in ADE integration:
 - Performance testing of the optimised (Rev B) peltier modules
 - EMC testing of the optimised (Rev C) PAF case



Pre-production ground planes bonded with Nomex dielectric & shrouds



Pre-production digital receiver, beamformer & correlator test installations in room 172



Bare rack




Beamformer Cards



Correlator

PAF front end production (cash flow dep.)



Production schedule under review to align with Puzzle's production line capacity

Funding

- Additional funds secured
 - \$6m from CSIRO capex
 - \$6m from SIEF
 - An additional \$6m CSIRO capex
 - Matching the AAL managed, NCRIS2 funds supporting ASKAP Operations
- Funded for:
 - 6 Mk I PAFs
 - 30 Mk II PAFs

Total = 36 PAFs
- Cash flow dependent manufacturing model
- Still working on sequence / plans to replace Mk I PAFs with Mk IIs
 - October 2014 workshop

*We acknowledge the Wajarri Yamatji people as
the traditional owners of the Observatory site.*

Thank you

CSIRO Astronomy and Space Science

Antony Schinckel

ASKAP Director

t +61 2 9372 4101

e antony.schinckel@csiro.au

w www.csiro.au/cass

CSIRO ASTRONOMY AND SPACE SCIENCE

www.csiro.au

