

# ASKAP

## Commissioning Update

### Dec 2013



# Commissioning Overview


- BETA – current status
- Recent results
- ADE / MkII commissioning
- ACES –  
“ASKAP Commissioning and Early  
Science”

# BETA status

- All six BETA antennas now operational (as of Sep 2013)
- Three newer antennas still being bedded-in
- Correlator currently in 3+3 configuration
- Data successfully taken with each 3-antenna subset
- Initial imaging tests gave poor results owing to h/w correlator artifacts and instability
- Firmware developers currently have priority access to rectify these faults



# BETA 1.5 → Full BETA



# First image with h/w correlator


Nov 2013

Standard test-field

h/w correlator with ants  
1 + 3 + 6


9 overlapping beams  
(c.f. red contour)

$F = 1\text{GHz}$ , 32MH b/w







# Remote observing begins at the SOC



# First HI detection with BETA (autocorrs)



# One day in the SOC






# Current activities

- Fixing minor hardware problem as they arise
- Learning to drive the hardware correlator
  - Debugging firmware using on-sky data and injected signals
  - Stress-testing the correlator software drivers
  - Testing delay tracking and fringe-rotator
  - Testing the “ingest pipeline” that records data to disk
  - Coming to grips with calibration
- Expanding knowledge and operator base of BETA
  - Enlarge commissioning group through “ACES”
  - Extensive discussion between commissioning and computing groups

# Data pipeline

- Still some way from full ASKAP data pipeline
- Additional s/w tools developed for commissioning






# New result: HI in absorption at $z=0.89$


PKS 1830-210 aka  
PKS 1830-211

The strongest radio gravlens


Multiple absorption systems,  
 $z=0.89$ ,  $z=0.19$



# Using PAFs for pointing correction



Before: *a priori* error =  $\sim 2.5d$




One iteration: error =  $\sim 0.3d$



# Upcoming priorities

- Repeat 3-antenna test image on BETA-2 (antennas 8,9,15)
- 6-antenna phase-closure and image on full BETA
- Early 2014: full BETA continuum image and simple spectral-line image released to SSTs.
- BETA remains engineering test-bed through to Q3 2014.
- ~March 2014 first field-tests of MkII PAF at MRO
- mid 2014: ADE-6 deployment commences
- 2<sup>nd</sup> half 2014: full ADE-6 continuum image and simple released to SSTs
- Early science program commences with ADE-12

# ADE / MkII PAF status: 5x4 test results



# PTF - Hot load/sky test track



# Full ADE test at MRO – early 2014



Hot load for ADE PAF ground tests *en route* to MRO



# ASKAP - schedule

- **Mk I**

- 6 BETA PAFs at MRO
- H/W correlator testing
- 3+3 configuration →
- 6 antenna config ~Feb 2014



- **Mk II**

- Prototype assembly: June – December 2013
- Field tests at MRO in Q1 2014
- First 6 production PAFs – Q2 2014
- 2<sup>nd</sup> 6 – Q4 2014
- Subsequent deliveries:
  - Optimum batch size being determined

# Parkes Test-Bed

- Successful results from ADE 5x4 test programme at Parkes – new ADE design now matches best achieved with earlier designs
- Continuing active programme of PAF observing and calibration using 64m-12m interferometer for calculating, manipulating and applying beam-former weights
- Brian Jeffs (Distinguished Visitor BYU) and CASS staff using PTB to develop active RFI weights for adaptive RFI mitigation
- PAF “bake-off” in 2014 between different types of PAF

# ACES –

## ASKAP COMMISSIONING AND EARLY SCIENCE

- Informal structure to assist in resourcing and planning of commissioning and early science

- Manager is Dave McConnell



- Aims to identify in-house and external resources to facilitate commissioning and early science programme

- Call for EOI to participate in secondments to ACES

*We acknowledge the Wajarri Yamatji people as  
the traditional owners of the Observatory site.*

# Thank you