



# **Update from SKA-Low Science Commissioning**

Giulia Macario
On behalf of the SKA-Low Science Commissioning team

CSIRO Space and Astronomy, Co-learnium Talk Series

6th October 2025



We recognise and acknowledge the Traditional Owners of the lands on which our facilities are located, and pay our respects to their Elders past and present.

Australia's Indigenous people are the first scientists and have long standing knowledge of the Universe that we continue to build on today.

We acknowledge the Wajarri Yamaji as the Traditional Owners and native title holders of Inyarrimanha Ilgari Bundara, the CSIRO Murchison Radio-astronomy Observatory, where we are building the SKA-Low telescope in Australia.


We acknowledge the Whadjuk Noongar as the traditional owners of the land where our Science Operations Centre is situated in Perth, and the Southern Yamatji as the traditional owners of the land where our Engineering Operations Centre is situated in Geraldton.

I also pay my respects to all First Nations people in attendance.




A collaborative painting from Aboriginal Yamaji artists from WA for the SKAO *Shared Sky* exhibition. Credit: Yamaji Arts Centre.





#### **How Commissioning fits in the big picture**

Science Commissioning focuses on tests of science capability, using astronomical observations



Includes Short Functional Tests (SFTs) Includes Test Cases, Verification Events, ... Structured around a Commissioning Plan for each Array Assembly Ensuring the telescope meets the needs of the science & operational users



## **SKA-Low staged delivery**

| Milestone Event                  | Low St | Low Stations |  |
|----------------------------------|--------|--------------|--|
| AA0.5                            | 4      |              |  |
| AA1                              | 16     |              |  |
| AA2                              | 68     | 96           |  |
| Science Verification begins 2027 |        |              |  |



As of today 14,512 antennas had been laid on ground (~11% of AA4)!

AA\* 307

Operations Readiness Review

End of Staged Delivery

Early Operations begin 2029 (shared risk)

AA4 (Full Design Baseline SKA1) 512



#### SKA-Low AA0.5 - layout

#### AA0.5 Complete!

- Four stations: S8-1, S8-6, S9-2 and S10-3
- Shortest baseline ~120m, longest ~5.5km
- Stations are rigidly rotated relative to each other
- Next milestone: AA1 (16 stations in the same clusters)



Four operational stations spread across the Southern spiral arm

#### Low Science Commissioning: Plans & progress


Based on set of ~40 commissioning tests for AA0.5 (defined and prioritised)

**Low AA0.5 Science Commissioning test progress** 

- <u>Fundamentals</u>: fringes/delays; closure; array calibration; cross calibration; quality of beams and bandpass; linearity; frequency accuracy and contiguity; RFI
- <u>Imaging</u>: full Stokes; sensitivity; stability of beams and bandpass; spectral line
- <u>Beamforming</u>: pointing; tracking; polarization alignment; sensitivity

Close collaboration with Science Operations to undertake test observations


- Joint planning/coordination meetings
- Shared documentation & logs



## **Science Commissioning focus areas**


- Single station performance
- Array beamforming performance
- Array calibration and imaging performance
- Development of SKA-Low Calibrator Database
- Software algorithms and workflows


## Single station behaviour



#### **Commissioning outcomes so far:**


- Good calibration solutions for each antenna within a station
- Stable performance with time and varying environmental conditions
- Per-antenna delays for pointing and tracking are fit for purpose
- Beam shape and sensitivity are approximately as expected







## **Low Science Commissioning: Pulsar detections**


- Detected 56 known pulsars so far using raw voltages from single stations
- Sneak peek at full polarisation properties, with promising results
- Initial testing of tied-array performance realtime calibration loop in development so full coherence not yet available















- Special version of dspsr performing Polyphase Filter Bank inversion
- Time resolution improved to 1.28 µs!


Credits: Willem van Straten, PST team


# **Basic array performance**



#### **Commissioning outcomes so far:**


- Interferometric fringes detected
- Per-station delays determined to be stable and match fibre lengths
- Closure phase verified (indicating that visibilities can be calibrated)
- Station sensitivities measured
- First images produced
- Station bandpasses determined






## Low AA0.5 visibilities: path to first image

- Excellent baseline sensitivity
- Progress with compensation for station rotation effect (Baseline between S8-1 & S10-3: relative angle 27.1°; B ~ 3.6 km)






Raw (unflagged!), delay calibrated and averaged data

## Low AA0.5 visibilities: path to first image


- Excellent baseline sensitivity
- Progress too with (self-)calibration ...

#### Unflagged data, after bandpass and gain (self-)calibration



# First SKA-Low AA0.5 image!

- Field surrounding PKS 0521-36 (~56 Jy at 150 MHz)
- 150-175 MHz BW
- 7 hours effective integration time
- Image noise
   ~5-6 mJy/beam
   at 70" final resolution
- 85 sources detected and matched to GLEAM-X catalog








## First Low AA0.5 image: comparison to GLEAM-X

 Self-calibration process was mostly unguided but produced a field with source fluxes that mainly line up very well with expectations!







#### **SKA-Low station SEFD**


SEFD is a measure of sensitivity: lower is better!

#### Estimated from S/N of pt src visibilities





# **SKA-Low Calibrator Database (ongoing effort)**




#### SciComm+SciOps outcomes so far:

- 23/38 compact isolated sources observed, across full 50-350 MHz
- Q&A plots of raw visibilities to support Operators
- Bandpass calibration tests for all sources (150-200 MHz only)
- Sky model tests with single point source, also with field sources
- Comparing legacy software (Miriad/CASA) and AO Calibrate
- Testing the developing SDP INST pipeline on real AA0.5 data
- Testing OSO tools
- Active planning is underway for Commissioning Calibrator Surveys

Goal: Build-up the SKA-Low calibrator list! Stage 1 of SKA-Low sky model

# First look at full BW calibration (3C273)









## **Recap: Science Commissioning outcomes**


Good single station calibration, pointing, tracking






Initial tied-array beam results in pulsar timing (PST) mode, with full coherence coming soon

Good array calibration demonstrated, with first images being produced





Development of calibrator database and testing the instrumental calibration pipeline



## **Science Commissioning status and next steps**

- So far, >80% of the planned AA0.5 commissioning tests are completed or significantly advanced; remainder carry over to AA1
- Now writing AA1 plans, with AA2 plans to be developed soon as well
- Developing updated Calibration Plan, and Commissioning Survey Plan
- Collaborating closely with several adjacent teams:
   Science Operations, AIV/Vulcan, System Science, and others





- More useful uptime
- More stations -> better calibration and sensitivity
- Better understanding of systematics
- Improved team processes



We recognise and acknowledge the Indigenous peoples and cultures that have traditionally lived on the lands on which our facilities are located.



www.skao.int