

Status of the Bonn Correlator

MPIfR – BKG correlator



Walter Alef
Helge Rottmann



Bonn correlator centre

- MK IV hardware correlator (XF)
 - 15 Mark 5s: 8 x 5A, 4 x 5B, (1 x 5B+, 2 x 5C)
 - Up to 1 Gbit/s data rate
 - 16 frequency channels
 - 32 lags (default continuum)
up to 1024 (tested)
 - Data export:
 - To AIPS using MK4IN
 - To geodetic database (CALC/SOLVE etc.)



Bonn correlator centre

- MK IV operations
 - GMVA observations at 83 GHz
 - 13 stations
 - 512 Mbit/s
 - 10 days per year
 - MPI-based observations
 - e.g. observations above 100 GHz
 - EVN observations with special requirements
 - Geodetic VLBI (~50%)
 - Handled by partner BKG and Uni Bonn



DiFX Software Correlator

present status

- Standard DiFX implementation
 - Input from Mark 5A/B or 20 TB Raid
 - 1 Gb via Internet possible + 1 Gb from Eb
 - Cluster with 176 compute cores in 22 nodes
 - 20 Gbit Infiniband interconnect
 - 1 Gb Ethernet
- Manpower:
 - open postdoc position with geodesists
 - H. Rottmann & W. Alef: very limited time available at present for work on DiFX



DiFX plans for 2008/2009

- Realise production system similar to MK IV / VLBA
- Verify geodetic quality of correlation
 - Implement phase-cal extraction
 - File output to MK IV format \Rightarrow database
- Phase-out MK IV correlator
- Add $>\sim 4$ Mark 5C
- Convert Mark 5A/B to Mark 5C



DiFX plans for 2008/2009

- Extend cluster to ~ 500 compute cores (November 2008)
 - More than ~10 stations @ 1 Gbit (1:1 in time)
- Direct rack cooling
- rebuild correlator room
- Manpower:
 - geodetic postdoc (hopefully soon)
 - H. Rottmann starting 03/09 full time on DiFX
 - J. Anderson for Lofar application



Upgrade plans for hardware

- ~16 Mark 5C
- Internet connectivity > 1 Gbit/s
 - Depending on demand
 - In 2012 10 Gbit/s ?
 - Big disk buffer: hundreds of TB
 - Asynchronous data transfer + Mark 5C mixed correlation



Geodetic correlation: needs

- massive subnetting
- typically only 1 frequency setup
 - except for cases with LO offset
- one start time, different stop times
- output 1 file per baseline/scan + station file + file root (vex excerpt) incl. Model
→ translation program needed
- “version control” of output files



MK IV correlator VEX files

- observe vex file + clocks + eop + pcal mode
- log vex file: station -> scan name > 8pack > file name (possibly byte position)
- correlator vex file: possible correlator setups
- experiment vex file: setup parameters for each experiment (int. time, lags, polarisations)
- vex file with setups for phase-cal extraction



geodetic correlation

- scan-based
- parallel sub-net correlation
- $n \times$ integration time fits in 1 minute
- scans of 20 s +, (soon even shorter)
- operator start script with scans
- mount requests for Mark 5 modules
- status display of playbacks and correlator
- export with data selection to CALC/SOLVE via DBEDIT



MK IV Output files

- Each scan creates a subdirectory with scan name
- Each correlation of scan creates root file with version as file extension (date encoded to base 26)
- each station has file with state counts and phase-cal
- each baseline has file with raw data
- each run of fringe fitter creates file for baseline and sub-frequency (S/X LL RR ...)







geodetic verification: step 1


- 30 s of data of 4 stations, 1 lower sideband
- The data was exported to AIPS
- comparison was done in MIRIAD
- The total phase as a function of frequency (delay) and the total phase over time were calculated
- The differences between the results of DiFX and the MK IV correlator were calculated



geodetic verification

- **Results:**
- the mean phase difference is well within 1σ of zero, and the
- r^2 values indicate that far less than 1% of the variation in the data can be explained by linear regression.
- Thus, no significant differences exist between the phase outputs as a function of time, between the MK IV and DiFX correlators.







Next step of comparison

- 1 h 3 station INT3 (Wettzell, Ny Ålesund, Tsukuba)

Problems encountered so far:

- “Illegal VLBA format” of translated Ts data.
- Non-standard track assignments of Ts
- Mark IV formatted Mark 5 data starting on integer second before scan starts.
- manual phase-cals.



Next step of comparison

- DiFX data export and fringe fitting via AIPS to data-base.
- Problems with importing to AIPS encountered due to “unusual” (=geodetic) frequency setup. Under investigation.
- Bonn and Leipzig analysis centres will perform CALC/SOLVE comparison.
- Results so far: looks good on first inspection



full geodetic verification

- phase-cal
- 24 h full geodetic run ~ 8 stations
- documentation of algorithm

Later:

- output to MK IV format